




Bijaynagar Rural Municipality
Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu
Lumbini Province, Nepal



BILL OF QUANTITIES (BOQ)

F.Y. : 2081/082

Date :

Project Name : Aadhuro Abdul Rajjak ko Ghar Dekhi Kalimai Than Saama Sadak Istarunnatri Wada No.7 & Lalpur Gaunn Ma Nali Nirmai
Location : Bijaynagar Rural Municipality-07, Ganeshpur (K.V.)

Project Name : Aadhuro Abdul Rajjak ko Ghar Dekhi Kalimai Than Saama Sadak Asta							Date :
Location : Bhaiynagar Rural Municipality-07, Ganeshpur (K.V.)							
S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
PROVISIONAL SUM							
A	Provide and installation of project information board	No	1.00	3,000.00	Three Thousand Only	3,000.00	
1	Provide additional tests for material and works as required and	ps	1.00	8,000.00	Eight Thousand Only	8,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)			Sub-Total A	Eleven Thousand only	11,000.00	
DRAIN CONSTRUCTION WORKS							
B	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	Cum	72.95				
2	One layer stone rolling on foundation/floor including watering and manual compaction work.	Cum	16.09				
3	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	8.58				
4	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam, lintel sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.Inclusive of Formworks	Cum	27.21				
5	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation, column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	Kg	1,509.17				

शोभा रसिनाल
प्रमुख प्रशासकीय अधिकृत



Total Amount With PS

Vat @ 13% (In with PS amount)

Grand Total Amount

Name of Firm :

Address :

Signature :

Seal :