



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu

Lumbini Province, Nepal

BILL OF QUANTITIES (BOQ)



शोभाराम रिजाल
प्रमुख प्रशासकीय अधिकृत

Project Name : Baddaur Gaun Bhitra Nali Nirman

Budget head : Nepal Sarkar Samanikaran Anudan (Page no.25, sn. 110)


Location : Bijaynagar Rural Municipality-06, Baddaur.

F/Y : 2081/082

Date:-

S.N	Description	Unit	Quantity	Rate,NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	Provisional Sum						
1	Provide and installation of project information board of size 1.20 m X 0.90 m along with iron posts including excavation, concreting, backfilling etc.	No.	1.00				
2	Carry out additional tests for material and works as required and instructed by the Project Manager/Engineer.(GCC 33.1)	PS	1.00				
	Sub-Total (A)						
B	ROAD SIDE DRAIN CONSTRUCTION WORK						
1	Earth work excavation in Ordinary Clay and silty soil for foundation trenches including shoring, strutting, bracing, sheeting and disposal upto 10 m, lift upto 1.50 m, and Back filling all complete work.	Cu.m	56.29				
2	Stone soling:Providing and laying, dry stone soling in floor with Stone complete to specified level including sand filling on joints as per design drawing and instruction of engineer	Cu.m	10.76				
3	Plain Cement Concrete : Providing and laying of PCC grade M10 (1:3:6) inclusive formworks, leveling, batching, placing in position, mechanical compaction, consolidation, finishing, curing etc. and all as per specification and instruction of engineer.	Cu.m	4.14				

गोभाराम रिजाल
प्रमुख प्रशासक

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.) प्रमुख प्रशासक	Remark
				In Figure	In Words		
4	PCC for RCC grade M20: Providing and laying of Plain/Reinforced Cement Concrete grade M20 (1:1.5:3) inclusive formworks, leveling, batching, placing in position, mechanical compaction, consolidation, finishing, curing etc. and all as per specification and instruction of engineer.	Cu.m	24.16				
5	Rebar: Reinforcement for RCC work including supplying, delivering and storing of various diameters as required at site of work transportation, unloading at site, straightening, cutting, bending, placing in position at any level, binding in position of steel reinforcements Fe-550D including cost of binding wire, labour, scaffolding, transportation to & from stores etc complete all as per specifications, drawings and as per instruction of engineer.	Kg	1,028.87				
Total Amount							
Vat @ 13%							
Grand Total Amount							

Name of Firm :

Address :

Signature :

Seal :