

Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khuruhuriya, Kapilvastu
Lumbini Province, Nepal
BILL OF QUANTITIES (BOQ)



शोभाराम शिवालय
 प्रमुख प्रशासनिक अधिकृत

Programme name :Rural Municipality Grant

Project Name : Mainari Bijay Prakash Tripathi ko ghar dekhi pakshim dakshin Baatoma Naali Nirman

Source of Budget : Nepla Sarkar-Samanikaran Anudan, Title no. 31151, s.no. 114

Location : Biajynagar Rural Municipality, Ward No. 03, Mainari (K.V.)

F.Y. : 2081/082

Date:-

S. N	Description	Unit	Quantity	Rate,NRs.		Total (NRs.)	Remark.
				In Figure	In Words		
1	Public Information Board	No	1.00				
2	Lab test as Instructed by Engineer	PS	1.00				
3	Earthwork excavation for ordinary soil lead 10 m and lift 1.5 m including disposal of unnessary materials.	Cu.m	51.30				
4	Dry Stone soling including sand sealing/ bedding & compaction.	Cu.m	9.50				
5	PCC work 'M10 Grade (1:3:6 mix by volume) Cement Concrete work in foundation including all labour and material required for mixing, placing in position, vibrating, compacting, finishing, curing and all other incidentals required for the concrete as per specification.	Cu.m	5.70				
6	M20 Grade (1:1.5:3 mix by volume) Cement Concrete work in foundation including all labour and material required for mixing, placing in position, vibrating, compacting, finishing, curing and all other incidentals required for the concrete as per specification.	Cu.m	20.04				
7	Reinforcement for R.C.C. work. It includes procuring steel, its bending, placing, binding and fixing in position as shown on the drawings as directed by Engineer. It also includes all devices for keeping reinforcement in approved position.	kg	1,006.14				

रामेश्वर रिजाल
प्रमुख प्रशासकीय अधिकृत

	Total Amount	
	Vat @ 13%	
	Grand Total Amount	

Name of Firm :

Address :

Signature :

Seal :

