



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
 Khuruhuriya, Kapilvastu
 Lumbini Province, Nepal



BILL OF QUANTITIES (BOQ)

Project : Wada Bhitra Sadak Istarunnati

Programme : Nepal Sarkar-Samanikaran Anudan(31151), Dosaro Gaun Sabha Ko Chhaito Adhibesan

Location : Bijaynagar Rural Municipality-7, K.V.

FY :- 2081/082

Date :

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Provide and installation of project information board As Per Site Incharge	No.	1.00	3,000.00	Three Thousands Only	3,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	PS	1.00	10,000.00	Ten Thousands Only	10,000.00	
	Sub-Total					13,000.00	
B	CONSTRUCTION WORKS OF ROAD SIDE DRAINE						
1	Excavation works: Earthwork in excavation of Foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved materials as per drawing and technical specification. (DoR SS 907) Ordinary Soil (up to 3m depth) by mechanical means	Sq.m	8.35				
2	Stone Soling Works: Providing and laying of hand pack Stone soling with 150 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (DoR SS 2000)	Cum	1.86				
3	PCC Works M10 : Providing and placing concrete M10 including compaction, curing, testing and lead. all complete, as per Drawings. (DoR SS 2000)	Cum	0.93				
4	PCC for RCC grade M20: Providing and laying of Plain/Reinforced Cement Concrete grade M20 (1:1.5:3) inclusive formworks, leveling, batching, placing in position, mechanical compaction, consolidation, finishing, curing etc. and all as per specification and instruction of engineer. (DoR SS 2000)	Cu.m	4.22				
5	Reinforcement Works: Providing and laying Reinforcement including cutting, bending, binding, fixing in position etc. all complete as per sepcification and drawing. (DoR SS 2014)	Cu.m	185.73				

(Signature)
शमशेर रिजाल
 प्रमुख प्रशासकीय अधिकृत

6	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications. (DoR SS 909, 910)	Cum	38.88				
7	Sub Base Course: Providing , laying , spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all complete (SS/SP-1201) and instruction of engineer	Sqm	149.11				
8	Supply and Laying Precast Cement Concrete Behton Interlocking I-Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above, Thickness : 60mm, Dimension : 200mm*165mm*60mm) inclding stone dust base and gap fill.	Cu.m	56.25				
Total Amount							
Vat @ 13% Of Total Amount With PS							
Grand Total Amount							

3
शोभाराम रिजाल
 प्रमुख प्रशासकीय अधिकृत

Name of Firm :

Address :

Signature :

Seal :

