

Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khuruhuriya, Kapilvastu
Lumbini Province, Nepal



बिजनगर गाउँपालिका
कार्यपालिकाको
इसतुहिया कपिलवस्तु
लुम्बिनी प्रदेश

BILL OF QUANTITIES (BOQ)

Project : Shankarpur Gaun purwa dekhi pashim jane bato Sadak Starunnati ,Jolahi tharu gaunko dhalan & Bargadawa Gaun Ko Paschim Tarpah Ko Culvert Ma Mato Patan Tatha Gravel

F.Y. : 2081/082

Location :- Bijaynagar Gaunpalika Ward No 4, Shankarpur, jolahi, Bargadwa

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Provide and installation of project information board As per Site Incharge	No	2.00	2,000.00	Two thousand only.	4,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	Job	1.00	10,000.00	Ten thousand only.	10,000.00	
	Sub-Total (A)					14,000.00	
B	Civil Works						
B.1	shankarpur Gaun purwa dekhi pashim jaane baato Sadak Stornati Bijaynagar -4 Kapilvastu						

29

बिजनगर गाउँपालिका
कार्यपालिकाको
इसतुहिया कपिलवस्तु
लुम्बिनी प्रदेश

1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness.(DoR SS 201)	Sq.m	1,493.50				
2	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	Cu.m	179.91				
3	Sub Base Course: Providing , laying , spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all complete (SS/SP-1201) and instruction of engineer	Cu.m	201.63				
B.2	Jolahi tharu gaunko adhuro p.c.c. dhalan						
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness.(DoR SS 201)	Sq.m	120.00				



सिंहाराम रिवा
महोदय कार्यालय अतिरिक्त

2	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) in foundation with cement, sand and stone ballast 20 mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cum	31.05			
B3	Bargadawa Gaun Ko Paschim Tarpha Ko Culvert Ma Mato Patan Tatha Gravel					
1	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications. (DoR SS 909, 910)	Cum	76.91			
2	Sub Base Course: Providing, laying, spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cu.m	9.84			
Sub Total Amount with PS						
VAT @ 13%						
Grand Total Amount with PS & VAT						


Name of Firm :

Address :

Signature :

Stamp:

[Handwritten Signature]



[Handwritten text: श्रीमान् विराट् पत्राचार्य]