



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khurhuriya, Kapilvastu
Lumbini Province, Nepal

BILL OF QUANTITIES (BOQ)

F.Y:-2081/082

Date:-

Project: Purano Parsasakiya Bhawan marmat tatha re-modling

Programme :

Location : Bijaynagar Rural Municipality

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
i	Provide and installation of project information board of size 1.20 m X 0.9 m along with iron posts including excavation, concreting, backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works. (DoR)	Nos	1	3,000.00	Five Thousand Only	3,000.00	
	Carry out additional tests for material and works as required and instructed by the Project Manager. (GCC 33.1)	PS	1	20,000.00	Twenty Thousand Only	20,000.00	
	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property. (GCC 13)	PS	1	20,000.00	Twenty Thousand Only	20,000.00	
						43,000.00	
B	CONSTRUCTION WORKS						
1	DISMANLING WORKS						
1.01	Dismantling R.C.C. or R.B.C. works and removing materials upto 10 m away from the site	Cu.m	0.24				
1.02	Dismantling of Truss & CGI Sheet roofing work including removing, upto 10m and stacking in proper place	Job	1.00				
1.03	Dismantling mud mortared masonry wall and removing materials upto 10 m away from the site	Curn	0.52				
2	CEMENT CONCRETE WORKS						




Shove Ram Rijal
Chief Administrative Officer

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
2.01	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam,	Cu.m	13.95				
3	REINFORCEMENT						
3.01	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20	Kg.	1,373.25				
4	FORMWORKS						
4.01	Centering and shuttering with plywood for Column including all necessary propping, scaffolding, staging,	Sq.m	4.14				
4.02	Centering and shuttering with plywood for Beam and Slab including all necessary propping, scaffolding, staging,	Sq.m	130.02				
5	MASONRY WORK						
5.01	Providing, laying and curing first class brick masonry works in cement, sand mortar (1:4) in super structure work of First	Cu.m	1.30				
6	PLASTERING & POINTING WORKS						
6.01	Providing, laying & curing 12.5 mm cement sand (1:4) Plastering on walls to perfect plumb, lines & level including	Sq.m	79.80				
6.02	Providing, laying & curing 12.5 mm thick cement sand (1:3) plastering in ceiling, beams surfaces including chipping &	Sq.m	92.92				
7	FLOOR FINISHING						
7.01	Providing, laying and curing 3mm thick (1:1) cement sand punning on floor of buildings on perfect line & level as per	Sq.m	56.73				
8	PAINTING WORKS						
8.01	Supplying and applying two coat interior premium emulsion paint with one coat interior wall primer.of approved brand	Sq.m	216.16				
8.02	Supplying and applying Two coat weather proof painting (Apex or equivalent) with one coat primer of approved	Sq.m	119.88				



Shova Ram Rijal
Chief Administrative Officer

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
8.03	Supplying And Applying 2 mm thick plain white wall Putting on wall or ceiling surface As Per Sitte Incharge.	Sq.m	56.73				
9	DOORS AND WINDOWS WORKS						
9.01	Making and fixing seasoned sal Wood chauhkat Wooden size (100 mm*75 mm). All complete as per specification, Design,	Cum	0.05				
9.02	Making and fixing sal Wood panelled shutters using 38 mm thick sal Wood frame	Sq.m	2.52				
9.03	Aluminium sliding window without ventilation with naturally anodized aluminium (section	Sq.ft	19.37				
9.03	Providing, making and fixing of MS Metal Windows using metal frame (L section angle 40*40*3mm), (20*5) mm angle	Sq.m	1.80				
10	Aluminium fix partition section size 65*35*1.2 net aluminium frame with 4mm thick aluminium composi	sqft	60.85				
11	Providing and fixing Hinged Door of section in natural or color anodized / powder coated color Section size (87 x 56 x	sqft	19.35				
12	ELECTRICAL WORKS						
12.01	Electrical wiring for Fan and Light Points with switch but without fixture including all labour and material like: 15 mm	Point	21.00				
12.02	Electrical wiring for 5Amp Power Points with switch & Socket including all labour and material like: 15 mm LDP	Nos	9.00				
12.03	48" Celing Fan fitting	Nos	4.00				
12.04	10 Watt LED Bulb	Nos	10.00				
12.05	5 Watt LED Bulb	Nos	7.00				
			Sub Total Amount With PS				
			Sub Total Amount Without PS				



Shovda Bam Rijal
Chief Administrative Officer

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
	Vat @ 13% Of Without PS Amount						
	Grand Total Amount (With Vat & PS)						

Name of Firm :

Address :

Signature :



Shova Ram Rijal
Chief Administrative Officer

Seal :

