

**Bijaynagar Rural Municipality**  
**Office of the Rural Municipal Executive**  
**Khuruhuriya, Kapilvastu**  
**Lumbini Province, Nepal**  
**BILL OF QUANTITIES (BOQ)**



शोभाराम रिजाल  
 प्रमुख प्रशासकीय अधिकृत

**Project :Baghmarwa Gaunko Biddyalaya Jane Bato Sadak Staronnati Ward No-5**  
**Programme : Rajswa Badphad Pradesh Sa rkar Nagad S.No.109, Page No.25 .**  
**Location : Bijaynagar Rural Municipality-05, K.V.**

F.Y. : 2081/082  
 Date:-

S.N	Description	Unit	Quantity	Rate,NRs.		Total (NRs.)	Remark.
				In Figure	In Words		
<b>A</b>	<b>PROVISIONAL SUM</b>						
1	Provide and installation of project information board	PS	1.00	2,000.00	Two Thousand Only	2,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	PS	1.00	6,000.00	Six Thousand Only	6,000.00	
<b>B</b>	<b>CONSTRUCTION OF GRAVEL ROAD</b>						
1	Construction of Subgrade and Earthen Shoulders with approved Material ( capping layer) Providing and laying sub-grade and earthen shoulders with approved Material obtained from borrow pits with all lifts & leads as per Drawing and Technical Specifications. ( DoR SS 1004)	Sq.m	522.00				
2	Sub Base Course: Providing , laying , spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all complete (SS/SP-1201) and instruction of engineer	Cu.m	62.64				
3	Supply and Laying Precast Cement Concrete Behton Interlocking I- Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above,Thickness : 60mm, Dimension : 200mm*165mm*60mm) inclding stone dust base and gap fill.	Sqm	142.75				

	Total Amount		
	Vat @ 13%		
	Grand Total Amount		

Name of Firm :

Address :

Signature :

Seal :



शोभाराम रिजाल  
प्रमुख प्रशासकीय अधिकृत

