

Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khurhuriya, Kapilvastu
Lumbini Province, Nepal
BILL OF QUANTITIES (BOQ)

Project : R.T.O Dekhi Mahadev Ward No 5 Birthing Center Samma Sadak Stornnati
Programme : antarik Shrot -nagad Yatayat Purbadhar S.No.88,Page No.24
Location : Bijaynagar Rural Municipality-05, K.V.

शोभाराम रिजाल
 प्रमुख प्रशासकीय अधिकृत



F.Y. : 2081/082
 Date:-

| S. N | Description | Unit | Quantity | Rate,NRs. | | Total (NRs.) | Remark. |
|----------|---|------|----------|-----------|--------------------|--------------|---------|
| | | | | In Figure | In Words | | |
| A | PROVISIONAL SUM | | | | | | |
| 1 | Provide and installation of project information board | PS | 1.00 | 2,000.00 | Two Thousand Only | 2,000.00 | |
| 2 | Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1) | PS | 1.00 | 5,000.00 | Five Thousand Only | 5,000.00 | |
| B | CONSTRUCTION OF GRAVEL ROAD | | | | | | |
| 1 | Construction of Subgrade and Earthen Shoulders with approved Material (capping layer) Providing and laying sub-grade and earthen shoulders with approved Material obtained from borrow pits with all lifts & leads as per Drawing and Technical Specifications. (DoR SS 1004) | Sq.m | 370.00 | | | | |
| 2 | Sub Base Course: Providing , laying , spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all complete (SS/SP-1201) and instruction of engineer | Cu.m | 37.00 | | | | |
| 3 | Supply and Laying Precast Cement Concrete Behton Interlocking I- Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above,Thickness : 60mm, Dimension : 200mm*165mm*60mm) inclding stone dust base and gap fill. | Sqm | 296.00 | | | | |

| | | | |
|--|--------------------|--|--|
| | Total Amount | | |
| | Vat @ 13% | | |
| | Grand Total Amount | | |

Name of Firm :

Address :

Signature :

Seal :



✓

शोभाराम रिजाल
मुख्य प्रशासकीय अधिकृत