



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khurhuria, Kapilvastu
Lumbini Province, Nepal



BILL OF QUANTITIES (BOQ)

Project: Geduwajot Lift Sicha Pipe Bistar
Programme : Dosro Gaun Sabha ko chhaitho Adhivesan ko Dosro Baithak ko Nirnay
Location : Bijaynagar Rural Municipality-07, Geduwajot

F.Y:-2081/082
Date:-

S.N	Description	Unit	Quantity	In Figure	Rate, NRs.		Total (NRs.)	Remark
					In Words			
A	PROVISIONAL SUM							
1	Provide and installation of project information as per site incharge	Nos	1.00	3,000.00	Three Thousand Only		3,000.00	
B	Civil Works							
1	Earthwork in excavation for foundation in ordinary soil including necessary lead and lift as per instruction of site engineer..	Cum	155.86					
2	Earthwork back filling with excavated soil in trench of foundation including consolidation in layers of 15 cm and watering as per instruction of site engineer.	Cum	93.52					
3	One layer stone solling on foundation/floor including watering and manual compaction work.	Cum	0.17					
4	Providing, laying, compacting and curing plain cement concrete M10 (1:3:6) in foundation with cement, sand and stone ballast 20 mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cum	0.47					
5	Providing, laying and curing first class brick masonry works in cement, sand mortar (1:6) in foundation in perfect lines & level as per specification, drawings & instructions of the site engineer.	Cum	0.36					
C	PIPELINE SUPPLY AND WATER SUPPLY							
1	Flange Set of 4"	Set	5.00					
2	G.I Elbow of 4"	Pcs	3.00					
3	G.I 4" T	Pcs	1.00					

श्रीभाराम रिजाल

प्रमुख प्रधानकोष अधिकृत
Total (NRs.)

S.N	Description	Unit	Quantity	Rate, NRs.		Remark
				In Figure	In Words	
4	GI Pipe Medium Class 100 mm (4") φ	Rm	15.00			
5	G.I 6" T	Pcs	2.00			
6	GI Pipe Medium Class of 150 mm (6") φ	Rm	21.00			
7	GI Elbow 150 mm (6")	Pcs	2.00			
8	CI Sluice Valve 4"	Pcs	1.00			
9	CI Sluice Valve 6"	Pcs	1.00			
10	GI/GI Flange Set of 6"	Set	8.00			
11	Gasket Rubber	Kg.	10.00			
12	Butterfly Switch	Pcs	2.00			
13	GI 4" Nipple	Pcs	4.00			
14	GI Endcap 100 mm (4")	Pcs	2.00			
15	Supply and Fixing of High Tensile nut bolt	Kg.	25.00			
16	UPVC Pipe Of 6" OF 4Kg/cm ² NS 206/046	Rm	346.00			
17	PVC T of 6"	Pcs	4.00			
18	PVC Bend of 6"	Pcs	6.00			
19	Solvent	Ltr.	5.00			
20	CI Non Return Valve 100 mm (4")	Pcs	1.00			
21	All extra and missing accessories for the supply, fixing and	Job	1.00			
Sub Total Amount With PS						
Vat @ 13% Of With PS Amount						
Grand Total Amount (With Vat & PS)						

Name of Firm :

Address :

Signature :

Seal :

