



**Bijaynagar Rural Municipality**  
Office of the Rural Municipal Executive  
Khuruhuriya, Kapilvastu  
Lumbini Province, Nepal



श्रीमराम रिजाल  
प्रमुख प्रशासकीय अधिकृत

**BILL OF QUANTITIES (BOQ)**

Project Name :- Pipari SamayaMai Mandir Nirman Tatha Byabasthapan  
Programme:- Rajaswo Bandfand-Sanghiya Sarkar-Nagad  
Location:- Bijaynagar Ward no 5 Kapilvastu

F/Y:- 2081/082  
Date :-

S.N	Description	Unit	Quantity	Rate,NRs.		Total (NRs.)	Remark
				In Figure	In Words		
<b>A</b>	<b>PROVISIONAL SUM</b>						
1	Provide and installation of project information board	Nos	1	1,500.00	One Thousand Five Hundred Only	1,500.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	PS	1	8,000.00	Eight Thousand Only	8,000.00	
	<b>Total PS Amount (A)</b>					<b>9,500.00</b>	
<b>B</b>	<b>CONSTRUCTION WORKS</b>						
1	Filling by stones in the foundation and levelling including haulage distance upto 30m	Cum	0.63				
2	M 10 Concreting of foundation, vertical faces walls (cement concrete) including supply of materials and haulage distance upto 30m.	Cum	0.32				
3	M 20 Concreting works of super structure deck slabs, beams including supply of materials and haulage distance upto 30m.(Manual)	Cum	25.80				
4	Cutting, bending, placing in position as shown in the drawing & binding by MS wire of reinforcement steel bar for RCC works incl. haulage dist. upto 30m	Kg.	2,579.84				
5	Making Wooden form work for slab and floor including supply and selection of materials fixing, nailing according to drawings, applying Primer, placing separators, oiling, dismantling forms and hauling upto 30 m distance	Sq.m	236.90				
6	Chimney (bhatta) brick masonry works along with supplying bricks making cement sand mortar and construction of brick wall including haulage distance upto 30m a) 1:4	Cum	5.62				
7	Electrical wiring for Fan and Light Points with LDP pipe, PVC box, switch etc	Point	17.00				

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
	Sub Total Amount With PS						
	Sub Total Amount Without PS						
	Vat @ 13% Of Without PS Amount						
	Grand Total Amount (With Vat & PS)						



Name of Firm :

Address :

Signature :

Seal :

*(Handwritten Signature)*  
 शोभाराम रिजाल  
 प्रमुख प्रशासकीय अधिकृत