



Bijaynagar Rural Municipality

Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu
Lumbini Province, Nepal



शोभाराम रिजाल
प्रमुख प्रशासकीय अधिकृत

FY :- 2081/082

Date :

BILL OF QUANTITIES (BOQ)

Project :Shree Samaymai sthan adhuro ground floor nirman tatha boundary wall plaster rangroan
Programme : Gaun karyapalika ko Baithak Sankhya 4 nirnaya no:6, S.N. 1
Location : Bijaynagar Rural Municipality-05, K.V.

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Provide and installation of project information board Asc Per site Incharge	No.	1.00	1,500.00	One Thousands Five Hundred Only	1,500.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	Job	1.00	5,000.00	Five Thousands Only	5,000.00	
B	Sub-Total					6,500.00	
	CIVIL WORKS						
1	PCC grade M15: Providing and laying of Plain Cement Concrete grade M15 (1:2:4) inclusive formworks, leveling, batching, placing in position, mechanical compaction, consolidation, finishing, curing etc. and all as per specification and instruction of engineer. (DoR SS 2000)	Cu.m	10.29				
2	Providing, laying & curing 12.5 mm cement sand (1:4) Plastering on walls to perfect plumb, lines & level including raking the mortar joints and wetting the masonry surface all complete as per design drawings, specifications and instruction of the site engineer all complete:	Sq.m	187.17				
3	Supplying and applying single coat exterior emulsion paint weatherproof (apex or equivalent) with one coat exterior wall primer.	Sq.m	96.79				
	Total Amount						
	Vat @ 13% Of Total Amount With PS						
	Grand Total Amount						

Name of Firm :

Address :

Signature :

Seal :